

MAYOR
Barbara Blain-Bellamy

MAYOR PRO TEM
Larry A. White



COUNCIL MEMBERS
Thomas J. "Tom" Anderson II
William M. Goldfinch IV
Shane Hubbard
Ashley Smith
Jean M. Timbes

PUBLIC WORKS DEPARTMENT

Addendum #2
Magnolia Maple Drainage HUD Project
Bid Package: 7-6-2018

TO: All Bidders

FROM: City of Conway Public Works
PO Box 1075
Conway, SC 29528
843-248-1730

DATE: June 27, 2018

All bidders submitting proposals for the above referenced project shall note the following changes to the drawings and/or specifications and all such shall become a part of the contract.

This Addendum consists of two (2) addendum sheets.
Items included in this addendum are the following questions & answers.

1. Are there any specifications for the project other than the bid package?
Specifications included the Civil Plan Set, SCDOT Permit and Referenced Drawing & Specifications, City of Conway Specifications.
2. Are there any Wetland Impacts and/or C.O.E. Permits?
City has wetland permits from S&ME
3. Are there SCDOT Permits?
Yes, attached.
4. The Construction Drawing Sheet C1 Note # 12 references a Soils Report. Is there one available?
No, Soils testing is required by the contractor in the SCDOT Right of Way.
5. What is the Pipe Bedding Material to consist of?
See SCDOT Improved Foundation Detail for pipe in SCDOT Right of Way. All others may be in situ if suitable or imported granular fill.
6. Can the Bedding Material of the improved Foundation consist of Structural Fill?
Yes, must be installed with all other requirements according to SCDOT Improved Foundation Detail attached with the plan set.

7. Is the typical Pipe installation outside the SCDOT R/W to be the same as the SCDOT requirements in regards to the bedding and backfill? Are all piping joints to be rubber gasketed?
No. Rubber Gasket RCP is required, but only on Grainger Road between Curb Inlet #1 & Curb Inlet #2.
8. What are the testing requirements for the compaction of the bedding and backfill inside and outside of the SCDOT R/W?
See SCDOT Quality Acceptance Sampling & Testing Guide for pipe/culvert backfill (Latest Edition).
9. What are the Clearing Limits? Can we remove the trees we think are needed for installation and equipment needs? **Yes.**
10. Can you give us a better description of what the Contractor's responsibilities are by Note#6 on Sheet C2, with determining the property lines if they could not be determined during the design? It doesn't look like the piping is following the adjacent property alignments as designed.
The City has drainage easements for the project. Engineer will provide construction staking plan to selected contractor.
11. Are there no existing utilities at the Magnolia Avenue road crossing?
At the tie-in location of the new boxes, no utilities were located by the surveyor or the City of Conway and none were visible at site inspections. Existing utilities may be present closer to the edge of pavement where the existing RCP's are crossing.
12. What is the scope of the asbestos water line relocation on Grainger Street? Should we plan to use 4-8" 45 Bends and DIP to raise the existing water line over the Storm Sewer with approx. 18" of cover.
City of Conway Water & Sewer will provide materials and modify the waterline once it has been uncovered.
13. Once the existing utilities are located at the Grainger Street crossing, what if any are the Contractor's financial responsibilities for any utilities that may need to be relocated?
It is expected the contractor would coordinate with all utility companies but would the relocation services and costs be by others?
City will pay for relocation.
14. What is the extent of the flowable fill in the 24" RCP on Grainger Street?
Yes, only the ex. 24" RCP's from the ditch to the first set of boxes.
15. What is the scope of work for Bid Item # 4?
Locate all utilities within the path of construction with PUPS and private utility locator.
16. Is there the possibility of only awarding one phase and could each phase be awarded to different contractors?
Only 1 contractor will be selected for the specified work. It is possible that only 1 phase will be selected.
17. On the Bid Tabulation near the end, there is only one item for Incidentals/Erosion Control so should you add an Item for each phase or should we combine both phases for a total?
Add an Item for each phase.

ACKNOWLEDGEMENT OF THIS ADDENDUM SHALL BE NOTED ON THE OFFICIAL BID FORM AND NOTED IN THE SUBMITTAL PACKAGE.